### सिडबी औरंगाबाद कार्यालय भूतल पर आंतरिक कार्य

#### Interior works on the ground floor of SIDBI Office Premises at Aurangabad

## (वित्तीय बोली / Financial Bid)

# प्रस्तुत करने की अंतिम तिथि 18.01.2023 को सायं 3 बजे तक / LAST DATE OF SUBMISSION 18.01.2023 UP TO 15.00 hrs

#### PROJECT:- PROPOSED INTERIOR WORK OF OFFICE FOR SIDBI AT ABC EAST AURANGABAD, MAHARASHTRA. REFER DWG NO. SHEET NO. SR.NO. DESCRIPTION QTY UNIT RATE **AMOUNT** Amount (in words) **PARTITION WORK** Α Providing & fixing wooden partition with fixed 1,187.00 SQ.FT 18 /19 /20 glass (excluding toughened glass area) Providing/fixing toughened glass 445.00 SQ.FT 18 /19 /20 /38 Providing/fixing gypsum partition 85.00 SQ.FT 3 18 /19 /20 Removing of existing front glass partition 1.00 Set **DOORS WORK** В Providing & fixing 35mm thk water proof flush door / patta Nos. 18 / 22 to be finished in 1mm thk laminate from both side with all necessary hardware fittings С **BLACKOUT ROLLER CURTAIN WORK** Providing & fixing blackout Roller curtain with all 601.00 SQ.FT 37 necessary hardware fitting (Vista/ Mac)

GLASS FROSTED FILM WORK

37

SQ.FT

115.00

D

Providing & fixing frosted linning glass film

without glitter with all necessary items

| Е        |   | (     | GLASS BO | ARD / PINUP BO | OARD / WHITE BOARD | WORK |    |
|----------|---|-------|----------|----------------|--------------------|------|----|
| 1        | Providing & fixing glass board with all necessary         | 32.00 |          |                |                    |      | 23 |
|          | items   |       |          |                |                    |      |    |
|          |   |       |          |                |                    |      |    |
| 2        | Providing & fixing pinup board with all necessary         | 74.00 | SQ.FT    |                |                    |      | 23 |
|          | items   |       |          |                |                    |      |    |
|          |   |       |          |                |                    |      |    |
| 3        | Providing & fixing white board with all necessary         | 26.00 | SQ.FT    |                |                    |      | 23 |
|          | items   |       |          |                |                    |      | 20 |
| -        |   |       |          |                |                    |      |    |
| F        |   |       |          | ELIDNITI       | JRE WORK           |      |    |
| 1        | Existing furniture to be shifted from old premises to new |       | l e      | FURINITI       | JRE WORK           |      |    |
| '        | premises with all necessary precaution including loading  |       |          |                |                    |      |    |
|          | and unloading (considering 3 trucks)                      | 3.00  | Nos.     |                |                    |      | -  |
|          | and unloading (considering 5 trucks)                      |       |          |                |                    |      |    |
|          |   |       |          |                |                    |      |    |
| 2        | Providing & fixing furniture work below kitchen           | 1.00  | Set      |                |                    |      | 21 |
|          | otta with all necessary items (for around 25 sq. ft.)     | 1.00  | Set      |                |                    |      | 21 |
|          | otta with an necessary items (for around 25 sq. ft.)      |       |          |                |                    |      |    |
|          |   |       |          |                |                    |      |    |
| 3        | Providing & fixing following new modular                  |       |          |                |                    |      |    |
|          | furniture with all necessary items                        |       |          |                |                    |      |    |
|          |   |       |          |                |                    |      |    |
| а        | Lunch Table   | 1     | No.      |                |                    |      | 24 |
|          |   |       |          |                |                    |      |    |
| b        | Full Ht Storage   | 5     | Nos.     |                |                    |      | 25 |
|          |   |       |          |                |                    |      |    |
| С        | AGM Cabin Low Ht Storage                                  | 1     | No.      |                |                    |      | 26 |
|          |   |       |          |                |                    |      |    |
| d        | AGM Cabin Side Table                                      | 1     | No.      |                |                    |      | 27 |
|          |   |       | _        |                |                    |      |    |
| е        | AGM Cabin Table   | 1     | No.      |                |                    |      | 28 |
| е        | AGIN Cabin Table  | '     | INO.     |                |                    |      | 20 |
|          |   |       | N        |                |                    |      |    |
| f        | Reception Area Corner Table                               | 1     | No.      |                |                    |      | 29 |
|          |   |       |          |                |                    |      |    |
| g        | Reception Table   | 1     | No.      |                |                    |      | 30 |
|          |   |       |          |                |                    |      |    |
| h        | Conference Low Ht Storage                                 | 2     | Nos.     |                |                    |      | 31 |
|          |   |       |          |                |                    |      |    |
| i        | Conference Table  | 1     | No.      |                |                    |      | 32 |
| <u> </u> |   |       | -        |                |                    |      |    |
| -:       | Staff Table   | 3     | Nos.     |                |                    |      | 33 |
| J        | Otali Table   | J     | INUS.    |                |                    |      | აა |
| <u> </u> | DOM Cabin Full Ha Marranta Davi                           |       | N.       |                |                    |      | 0. |
| k        | DGM Cabin Full Ht Momanto Rack                            | 1     | No.      |                |                    |      | 34 |

|          | DGM Cabin Low Ht Storage   | 1    | No.  |              |           | 0.5            |
|----------|--|------|------|--------------|-----------|----------------|
| ı        | DGM Cabin Low Ht Storage   | ı    | INO. |              |           | 35             |
|          |  |      |      |              |           |                |
| m        | DGM Cabin Side Table   | 1    | No.  |              |           | 36             |
|          |  |      |      |              |           |                |
| 6        | Providing & fixing catlog stand with all                               | 1    | No.  |              |           | 10.1           |
|          | necessary items refer photo  |      |      |              |           |                |
|          |  |      |      |              |           |                |
| 7        | Providing & fixing news paper stand with all                           | 1    | No.  |              |           | 10.1           |
|          | necessary items refer photo  |      |      |              |           | 10.1           |
|          | necessary items refer prioto   |      |      |              |           |                |
|          |  |      |      | <u> </u>     |           |                |
| G        |  |      |      | ELECTR       | ICAL WORK |                |
| 1        | Providing & fixing all electrical work as per                          | 1.00 | Set  |              |           | 16 / 17 / List |
|          | instructions by Architect on site & all drawings                       |      |      |              |           |                |
|          | please follow below points.  |      |      |              |           |                |
|          | produce folion bottom pointo.  |      |      |              |           |                |
| 2        | Providing & fixing separate pipe for elctrical                         |      |      |              |           |                |
|          | wire,computer wire,telephone wire,camera                               |      |      |              |           |                |
|          | wire,Computer wire,telephone wire,camera wire,T.V wire, HDMI wire etc. |      |      |              |           |                |
|          | WIFE, I.V WIFE, HOWI WIFE etc.   |      |      |              |           |                |
|          |  |      |      |              |           |                |
| 3        | Providing & fixing lighting / point wiring as per                      |      |      |              |           |                |
|          | detail list with all necessary material                                |      |      |              |           |                |
|          |  |      |      |              |           |                |
| 4        | Providing & fixing all computer lan point / raw point on               |      |      |              |           |                |
| <u> </u> | UPS & all electrical points on inverter                                |      |      |              |           |                |
|          | with all necessary items (board to board)                              |      |      |              |           |                |
|          | Country (Country Country)  |      |      |              |           |                |
| 5        | Providing & fixing computer lan / telephone / UPS /                    |      |      |              |           |                |
| 3        | camera / A/C & other point as per detail                               |      |      |              |           |                |
|          | list with all necessary material                                       |      |      |              |           |                |
|          | list with all necessary material                                       |      |      |              |           |                |
|          |  |      |      |              |           |                |
| 6        | Providing & fixing following items with all necessary items            |      |      |              |           |                |
|          | in electrical room that are 8  |      |      |              |           |                |
|          | way TPN -1 no , 12 way SPN - 1 no., 6-32 A / 10 A                      |      |      |              |           |                |
|          | SPMCB - 40 no.,40 A-63 A TPN MCB - 2nos.,                              |      |      |              |           |                |
|          | 25 A-32 A DP - 2 nos. and as per site                                  |      |      |              |           |                |
|          | requirement  |      |      |              |           |                |
|          |  |      |      |              |           |                |
| 7        | Providing & fixing complete work of electrical                         |      |      |              |           |                |
|          | room refer drawing   |      |      |              |           |                |
|          | -  |      |      |              |           |                |
| 8        | Providing & fixing generator cable work / earthing work as             |      |      | <del> </del> |           | 1              |
| O        | per site requirement & client  |      |      |              |           |                |
|          | decision with all necessary items (if applicable)                      |      |      |              |           |                |
|          | decision with all necessary items (ii applicable)                      |      |      |              |           |                |
|          |  |      |      |              |           |                |

| 9        | Providing & fixing anchor roma switches &                  |    |       |            |                    |   |                |
|----------|--|----|-------|------------|--------------------|---|----------------|
|          | accessaries refer detail list discusses about modules with |    |       |            |                    |   |                |
|          | Architect  |    |       |            |                    |   |                |
|          |  |    |       |            |                    |   |                |
| 10       | Shifting work of existing inverter / battery / stand       |    |       |            |                    |   |                |
|          | / server rack from old premises to new premises with all   |    |       |            |                    |   |                |
|          | necessary items  |    |       |            |                    |   |                |
|          | ,  |    |       |            |                    |   |                |
| 11       | Providing & fixing extra work / misceleaneous work as      |    |       |            |                    |   |                |
|          | per site decision & client decision with                   |    |       |            |                    |   |                |
|          | all necessary items  |    |       |            |                    |   |                |
|          | •  |    |       |            |                    |   |                |
| 12       | Providing & fixing HDMI cable with all necessary           |    |       |            |                    |   |                |
|          | litems.  |    |       |            |                    |   |                |
|          |  |    |       |            |                    |   |                |
| 13       | Providing & fixing burglar alarm system with all           |    |       |            |                    |   |                |
|          | necessary items.   |    |       |            |                    |   |                |
|          | necessary neme.  |    |       |            |                    |   |                |
| 14       | Providing & fixing patch cables 1.5 m long for all         |    |       |            |                    |   |                |
| 14       | workstation with all necessary items.                      |    |       |            |                    |   |                |
|          | workstation with all necessary items.                      |    |       |            |                    |   |                |
| Н        |  |    |       | FLECTRICAL | I<br>FIXTURES WORK |   |                |
|          |  | l  | I     | ELECTRICAL | -IXTURES WORK      | T | 10             |
| 1        | Providing & fixing electrical fixtures with all            |    |       |            |                    |   | 16             |
|          | necessary items  |    |       |            |                    |   |                |
| а        | LED panel light 2' x 2'                                    | 49 | Nos.  |            |                    |   |                |
|          |  |    |       |            |                    |   |                |
| b        | LED COB light  | 21 | Nos.  |            |                    |   |                |
|          |  |    |       |            |                    |   |                |
| С        | Ceiling fan 2' Ø   | 1  | NO.   |            |                    |   |                |
|          |  |    |       |            |                    |   |                |
| d        | Ceiling fan 3' Ø   | 3  | Nos.  |            |                    |   |                |
|          |  |    |       |            |                    |   |                |
| е        | Outdoor LED COB light                                      | 6  | Nos.  |            |                    |   |                |
|          | Cutacor LLD CCD light                                      | -  |       |            |                    |   |                |
| f        | Exhaust fan 200 mm ventilus high speed                     | 2  | Nos.  | 1          |                    |   | -              |
| <u>'</u> | crompton greaves   | _  |       |            |                    |   |                |
| <u> </u> | Wall fan 400 mm high speed TORPEDO                         | 12 | Nos.  |            |                    |   |                |
| g        | crompton greaves   | 12 | 1105. | 1          |                    |   |                |
|          | crompton greaves   |    |       |            |                    |   |                |
|          |  | L  |       | EDAD       | X WORK             |   |                |
|          |  |    |       | EPAB       | A VVUITN           |   |                |
| 4        | Droviding 9 fiving EDADY overteen with all                 | 4  | Cat   |            | 1                  | 1 | 17/05          |
| 1        | Providing & fixing EPABX system with all                   | 1  | Set   |            |                    |   | 17 / sheet - 1 |
| 1        | Providing & fixing EPABX system with all necessary items   | 1  | Set   |            |                    |   | 17 / sheet - 1 |
| 1        |  | 1  | Set   |            |                    |   | 17 / sheet - 1 |

| J |   |    |      | CCTV WORK |  |
|---|---|----|------|-----------|--|
| 1 | Providing & fixing CCTV camera with all   | 1  | Set  |           | 16/ sheet - 2/3/                             |
|   | necessary items   |    |      |           |  |
|   |   |    |      |           |  |
| < |   |    |      | A/C WORK  |  |
|   | 1 Providing & fixing 14 HP VRF unit system with all necessary items   | 1  | Set  |           | 16 / 17 / sheet - Refer SHEET AC Work for mo |
|   | Providing Indoor Units  |    |      |           | details                                      |
|   | Conference Room/ AGM cabin - 1.5 TR   | 2  | No.  |           |  |
|   | DGM Cabin, Staff, CSA, Concurrent Auditor - 2.5 TR  | 3  | Nos. |           |  |
|   | Electrical Server - 1 TR  | 1  | No.  |           |  |
|   | Providing & fixing individual split A/C in kitchen with all necessary items 1.5 TR (as per client decision)   | 1  | No.  |           |  |
| 2 | Installation of 14 HP Discharge Condensing Unit   | 1  | Set  |           |  |
|   |   |    |      |           |  |
|   | Installation of Casset AC   | 6  | Nos  |           |  |
|   | Installation of High Wall Ac  | 1  | Nos  |           |  |
|   | Supply and Intallation of Hard Copper Piping between Indoor and out door Units with 16/13mm thick Nitrile rubber Insulation for suction line without insulation alongwith Support | 80 | Mtr  |           |  |
|   | Supply and Intallation of PVC drain Piping with 6mm thick Nitrile rubber isulation  | 60 | Mtr  |           |  |
|   | Supply and Installation of power & Communication cable of between Indoor Unit and Outdoor.  | 70 | Mtr  |           |  |
|   | Pressure testing, Vaccumizing, Commissioning and additional Gas Charging  | 1  | Nos  |           |  |

| 1 | Complete and Installation of NAC fabricated stand for              |      | 1        | I            | 1                | =        | İ                   |
|---|--|------|----------|--------------|------------------|----------|---------------------|
|   | Supply and Installation of MS fabricated stand for condensing unit | 1    | Nos      |              |                  |          |                     |
|   | condensing unit  |      |          |              |                  | _        |                     |
|   | Lifting, Shifting of VRF Condensing Unit                           | 1    | Nos      |              |                  | =        |                     |
|   | g,gg   |      |          |              |                  |          |                     |
| L |  |      | PROJ     | ECTOR & PROJ | ECTOR SCREEN WOR | RK       |                     |
| 1 | Providing & fixing projector & projector screen                    | 1    | Set      |              |                  |          | 16 / 17 / sheet - 6 |
|   | with all necessary items   |      |          |              |                  |          |                     |
|   |  |      |          |              |                  |          |                     |
| М |  |      |          | CHAIR & S    | SOFA WORK        |          |                     |
| 1 | Providing & fixing Chairs &Sofa as per SIDBI design &              |      |          |              |                  |          |                     |
|   | specification with all necessary items                             |      |          |              |                  |          |                     |
|   | Company : Godrej / Feather Lite                                    |      |          |              |                  |          |                     |
|   |  |      |          |              |                  |          |                     |
| а | High Back Chair (base rate - 9000)                                 | 2    | Nos.     |              |                  |          |                     |
|   |  |      |          |              |                  |          |                     |
| b | Medium Back Chair (basic rate - 6500)                              | 40   | Nos.     |              |                  |          |                     |
|   |  |      |          |              |                  |          |                     |
| С | Lunch Table Chair (basic rate - 2500)                              | 7    | Nos.     |              |                  |          |                     |
|   |  |      |          |              |                  |          |                     |
| d | Three Seater Sofa (basic rate - 40000)                             | 1    | No.      |              |                  |          |                     |
|   |  |      |          |              |                  |          |                     |
| е | Two Seater Sofa (basic rate - 28000)                               | 1    | No.      |              |                  |          |                     |
|   | Basic rate are exclusive of GST, Bank may ask                      |      |          |              |                  |          |                     |
|   | for invoice for verificatiom                                       |      |          |              |                  |          |                     |
| N | TOT IN TOTAL TOT TOTAL TOTAL                                       |      | <u> </u> | DEED CLE     | ANING WORK       |          |                     |
| 1 | Providing & fixing deep cleaning work after completion of          | 1    | Nos.     |              |                  | 1        |                     |
| ' | all interior & instruction by an                                   | 1    | 1100.    |              |                  |          |                     |
|   | Architect on site with all necessary items                         |      |          |              |                  |          |                     |
|   | , ,  |      |          |              |                  |          |                     |
| 0 |  |      |          | TILES COV    | ERING WORK       | <u>'</u> |                     |
| 1 | Providing & fixing plastic panni always on existing tile for       | 2000 | SQ.FT.   |              |                  |          |                     |
|   | protection of tiles & granite with all necessary items upto        |      |          |              |                  |          |                     |
|   | finalisation of interior   |      |          |              |                  |          |                     |
|   | work   |      |          |              |                  |          |                     |
|   |  |      |          |              |                  |          |                     |

| Р | LANDSCAPE WORK   |     |        |             |              |  |  |  |  |  |
|---|--|-----|--------|-------------|--------------|--|--|--|--|--|
| 1 | Providing & fixing artificial vertical garden on                                     | 100 | SQ.FT. |             |              |  |  |  |  |  |
|   | existing left & right side ACP on outside otta with all                              |     |        |             |              |  |  |  |  |  |
|   | necessary items  |     |        |             |              |  |  |  |  |  |
|   |  |     |        |             |              |  |  |  |  |  |
| 2 | Providing & fixing artificial indoor plants with 12" ht round                        | 10  | Nos.   |             |              |  |  |  |  |  |
|   | white planters as per SIDBI design & specification with all necessary items & as per |     |        |             |              |  |  |  |  |  |
|   | Architect/ Bank approval. HT= 4'-5'  |     |        |             |              |  |  |  |  |  |
|   | Architect Bank approval. 111 = 4 3   |     |        |             |              |  |  |  |  |  |
|   |  |     |        |             |              |  |  |  |  |  |
| Q |  |     |        | ATTENDANCE  | MACHINE WORK |  |  |  |  |  |
| 1 | Providing & fixing fingerprint time & attendance with                                | 1   | Set    |             |              |  |  |  |  |  |
|   | access control system with all necessary items.                                      |     |        |             |              |  |  |  |  |  |
|   | Company name: ESSL   |     |        |             |              |  |  |  |  |  |
|   | Model: k30+ID+B (biometric / card based).B stands for battery.                       |     |        |             |              |  |  |  |  |  |
|   | Dattery.   |     |        |             |              |  |  |  |  |  |
| R |  |     |        | FIRE EXTING | BUISHER WORK |  |  |  |  |  |
| 1 | Providing & fixing manual fire extinguisher with                                     |     | I      | TINE EXTING | I            |  |  |  |  |  |
| ı | all necessary items. Refer photo   |     |        |             |              |  |  |  |  |  |
|   | all flecessary items. Refer prioro   |     |        |             |              |  |  |  |  |  |
|   | 01 ADO 51 5 11 11  |     | NI     |             |              |  |  |  |  |  |
|   | 2kg ABC Fire Extinguisher  | 2   | Nos.   |             |              |  |  |  |  |  |
|   |  |     |        |             |              |  |  |  |  |  |
|   | 4kg ABC Fire Extinguisher  | 2   | Nos.   |             |              |  |  |  |  |  |
|   | Make - Safepro / Safex / Ceasefire   |     |        |             |              |  |  |  |  |  |
|   |  |     |        |             |              |  |  |  |  |  |

| S | MAGNETIC LOCK WORK  |    |          |                            |                    |      |    |  |  |  |
|---|---|----|----------|----------------------------|--------------------|------|----|--|--|--|
| 1 | Providing & fixing frameless glass door / magnetic lock   | 1  | Set      |                            |                    |      |    |  |  |  |
|   | with all necessary items Company name : ESSL              |    |          |                            |                    |      |    |  |  |  |
|   | Model : BL99-7.   |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |
| 2 | Providing & fixing access card for punching               | 25 | Nos.     |                            |                    |      |    |  |  |  |
|   | with all necessary items                                  |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |
| Т |   | G  | ENTS TIO | LET TOUGHENI               | ED GLASS PARTITION | WORK |    |  |  |  |
| 1 | Providing & fixing toughened glass partition in           | 1  | Set      |                            |                    |      | 39 |  |  |  |
|   | gents tiolet w.c area with all necessary items            |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |
| U |   |    | CEILIN   | <mark>IG MOUNT WI-F</mark> | I ACCESS POINT WOR | RK   |    |  |  |  |
| 1 | Providing & fixing ceiling mount wi-fi access system with | 1  | Set      |                            |                    |      |    |  |  |  |
|   | cat 6 cables from internet junction & power point & all   |    |          |                            |                    |      |    |  |  |  |
|   | necessary items.  |    |          |                            |                    |      |    |  |  |  |
|   | Company : Grandstream (US)                                |    |          |                            |                    |      |    |  |  |  |
|   | Model : GWN7660   |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |
|   | TOTAL PROJECT COST (EXCL GST)                             |    |          |                            |                    |      |    |  |  |  |
|   | TOTAL PRODUCT COOT (EACH GOT)                             |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |
|   |   |    |          |                            |                    |      |    |  |  |  |

GST will be paid by Bank over and above the quoted rate as applicable.