

CONSTRUCTION OF SIDBI OFFICE AT GUWAHATI					
ESTIMATE FOR INTERIOR WORKS					
SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
1	CIVIL WORK				
1.1.	Dismantling and cutting of existing brick wall and removing the debris away from site	sqm	3		
1.2	Providing and making 115 mm thk brickwall in cement mortar 1:5 with 2 nos of 6mm reinforcement bars after every third coarse. The rate will include lintels above door etc including scaffolding complete in all respects.	sqm	60		
1.3	Providing and and applying 15mm thk. cement plaster in 1:5 ratio including curing complete in all respect	sqm	112		
1.4	Providing & finishing with two cement based putty of average thk. 1 mm. over cement plaster and gypsum ceiling in line & plumb finished extra smooth to receive paint of desired thickness	sqm	650		
1.5	Providing and applying acrylic emulsion paint having VOC (ICI / nerolac / Asian Paints) on walls and gypboard/POP ceiling including surface preparation, primer coats, levelling patti and minimum 2 coats of brush and roller finish.	sqm	750		
1.6	Providing and applying Texture Paint (rustic finish) with required base coat over 2 coats of oil primer complete in all respect.	sqm	66		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
2	FALSE CEILING WORK				
2.1	Plain gypsum ceiling	sqm	198		
	The ceiling shall be of plain gypsum sheets using GI framework.				
	The thickness of the gypboard sheet will be 12.5mm minimum. The framework shall consist of GI channel framework. The perimeter channel will be of 24 to 26 gauge having one flange of 20mm and other 30mm and web 27mm along the perimeter of the ceiling. It shall be screw fixed to brick wall with the help of rawl plug of dimension 38mmx12mm dia. fixed into the soffit at 610mm centers.				
	The intermediate channels of size 45mmx0.9mm thick with two flanges of 15mm each shall be suspended from ceiling using angle of size 25mmx10mmx0.55mm spaced not more than 1220mm c/c which are fixed to soffit with GI 27mmx37mmx25mmx1.6mm cleat and steel expansion fasteners. Ceiling section of 0.55mm thickness having curled web of 80mm and two flanges of 26mm are fixed to intermediate channel with the help of connecting clip of 2.64mm dia. in the direction perpendicular to intermediate channel at 457mm center to center.				
	No additional load like light fittings etc. shall be directly put on the ceiling frame. Separate suspension system shall be adopted for the same.				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	The ceiling plasterboard shall be fixed to the ceiling section using 3.5x25mm corrosion resistant self-tapping zinc plated dry wall screw at 230mm centers. Suspension ceiling angle shall be fixed firmly, vertically straight and tightly fixed to the framework by means of nuts and bolts. No one shall be allowed to walk over the ceiling system. it Shall be finished with recommended fillers, paper tapes, finisher and two coats of primer suitable for gypsum board, one coat of putty and two coats of Plastic emulsion paint. Refer schedule of Interior, furniture & finishes. Shall have grooves in two levels, cutouts for lights and AC grills as per drwgs. The ceiling shall be in perfect level and smooth finished. Shall have edge groove details and cove lighting provisions as per drwgs. The enclosed drawing should be followed for the arrangement of the false ceiling and the supporting systems.				
2.2	Gypsum Cove/Decorative Ceiling	sqm	40		
	Specification will be same as Item no.1.1. as per reflected ceiling plan . The ceiling will have provision of direct and in-direct lighting system. Measurement will be done on flat floor area basis				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
2.3	Grid ceiling	sqm	50		
	The grid false ceiling shall be provided in the workstation area, executive room etc. Refer drwgs. The ceiling height and level shall be determined at the perimeter. The minimum height of the ceiling cavity should be 100mm. All service fittings integrated within the suspended ceiling must be independently supported from the ceiling grid by a structure designed for the purpose.				
	Ceiling Tiles Shall be Armstrong Fine fissured Classic lite RH99 of min 14 mm thickness. Suspension system Shall be of Armstrong Trulok Silhouette reveal profile grid system with 15mm flanges incorporating 3mm central recess in global white with black reveal. Silhouette main runners and cross tees to have mitred ends and "birdsmouth" notches to provide mitred cruciform junctions.				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	<p>◆ Installation</p> <p>Main runners will be placed at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers and not more than 150mm from spliced joints. The last runner at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200mm long cross tees to be interlock between main runners at 600mm centers to form 1200x600mm modules. Cross tees longer than 600mm require independent support. 600x600mm modules to be formed by fitting 600mm long cross tees centrally between the 1200mm cross tees. The 1200mm cross tees to have central “birdsmouth” notches to facilitate fitting of 600mm cross tees. The perimeter trim to be Armstrong Trulok equal wall angle of white color</p>				
3	PARTITIONS				
3.1	Full ht. 69 mm. thk Solid partitions with both side Laminate	sqm	38		
	<p>Providing Aluminium frame (INDIAL/JINDAL) of size 50x50 x1.8 mm thk (finished) comprising of horizontals and verticals at, 600 mm c/c or part thereof with insertion of 50 mm thk glass wool, vertically and horizontally fixed firmly to walls / floors / RCC roof etc. Alternate vertical members to go upto RCC ceiling and firmly fixed.</p>				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	Providing 8 mm thk. ISI grade plywood of approved make , finished / fixed with 1 mm thick laminate of approved make & shade fixed with adhesive , fixed on both sides of the partition framework. The laminate to be fixed with adhesive on both sides of the partition upto False ceiling level .				
	The cost to include provision for extra framewark as necessary to make provision for skirting, switch boxes, light fittings/ lights etc, making provision for laying conduit etc.				
	NOTE : For measurement of the area of the partition , the height upto False ceiling will be considered. Makes: boards /ply :Century / Fiden/Austin, Laminate:- Century/ Signature/Elvee				
3.2	Full Ht. 69 mm. Thk. Solid partitions with one side SF Laminate finish and the other side with Imm thk Texturer finish	sqm	12		
	Specification will remain same as Item no.3.1 with 1 mm thick approved laminate in one side and 1 mm thk Texture finish laminate on the other side				
3.3	Full Ht. 69 mm thk.semi-glazed partitions with one side I mm thk Laminate finish and the other side with Texture Laminate finish	sqm	21		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	Providing Aluminium frame (INDIAL/JINDAL) of size 50x50 x1.8 mm thk (finished) comprising of horizontals and verticals at, 600 mm c/c or part thereof with insertion of 50 mm thk glass wool, vertically and horizontally fixed firmly to walls / floors / RCC roof etc. Alternate vertical members to go upto RCC ceiling and firmly fixed.				
	Providing 8 mm thk. ISI grade plywood of approved make, fixed on both sides of the salwood partition framework, finished with 1 mm thick SF laminate of approved make & shade on one side and 1 mm thick Texture finish laminate on other side The laminate & veneer to be fixed with adhesive on both sides of the partition upto False ceiling level. (only for bottom and top panel)				
	The partition will be provided with 8 mm thick clear float glass fixed with Edge Banding/T.W. lipping all round as per drawing. The veneer and Lipping to be further finished with melamine/PU polish complete as per instruction at site				
	The cost to include provision for extra framework as necessary to make provision for skirting, switch boxes, light fittings/ lights etc, making provision for laying conduit etc.				
	NOTE : For measurement of the area of the partition , the height upto False ceiling will be considered. Makes: boards /ply :Century / Fiden/Austin, Laminate:- Century/ Signature/Elvee . Veneer : Century, Green				
3.4	Low ht. 69 mm. thk. Solid partitions with both side Laminate	sqm	12		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	Providing Aluminium frame (INDIAL/JINDAL) of size 50x50 x1.8 mm thk (finished) comprising of horizontals and verticals at, 600 mm c/c or part thereof with insertion of 50 mm thk glass wool, vertically and horizontally fixed firmly to walls / floors / RCC roof etc. Alternate vertical members to go upto RCC ceiling and firmly fixed.				
	Providing 8 mm thk. ISI 303 grade plywood of approved make , finished / fixed with 1 mm thick laminate of approved make & shade fixed with adhesive , fixed on both sides of the partition framework. The laminate to be fixed with adhesive on both sides of the partition .				
	The cost to include provision for extra framewark as necessary to make provision for skirting, switch boxes, light fittings/ lights etc, making provision for laying conduit etc.				
3.5	Low ht. 69 mm. thk. glazed partitions with both side Laminate	sqm	11		
	Providing Aluminium frame (INDIAL/JINDAL) of size 50x50 x1.8 mm thk (finished) comprising of horizontals and verticals at, 600 mm c/c or part thereof with insertion of 50 mm thk glass wool, vertically and horizontally fixed firmly to walls / floors / RCC roof etc.				
	Providing 8 mm thk. IS 303 grade plywood of approved make , finished / fixed with 1 mm thick laminate of approved make & shade fixed with adhesive , fixed on both sides of the partition framework. The laminate to be fixed with adhesive on both sides of the partition.				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	The partition will be provided with 8 mm thick clear float glass of size approx.as per pattern shown in drawing with matching edge banding/ Tw beading finished with pU polish beading of size 19 X 27 mm approx. duly melamine polished				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	The cost to include provision for extra framework as necessary to make provision for skirting, switch boxes, light fittings/ lights etc, making provision for laying conduit etc.				
3.6	Designer partition	sqm	16		
	Providing and Making of Designer partition wall for Reception Backdrop with the use of 50x50x1.8 mm thk. Aluminium frames along with insertion of 50 mm glass wool within horizontal and vertical members 600 mm c/c. The entire framed structure will be cladded with 8 mm thk. MDF board as per the drawing and will have provision for Texture paint/ wall paper finish. The Reception backdrop will further have a Laquered glass with printed designs (1.2 x1.95 mm.) inserted within a framed panel . The slits created in the partition will further have 3 nos Laquered glass (1.5 x 0.2 m) inserted along the line as shown in the drawing. Rate will include all provision of cut-outs in the partition wall including moulding and pelmets as shown in the drawing				
4	WALL PANELLING				
4.1	Wall panelling with 8 mm thk ply with laminate finish (S.F.)	sqm	40		
	Providing Aluminium frame (INDIAL/JINDAL) of size 50x25 x1.8 mm thk (finished) comprising of horizontals and verticals at, 600 mm c/c or part thereof with insertion of 25 mm thk glass wool, vertically and horizontally fixed firmly to walls / floors / RCC roof etc.				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	Providing 8 mm thk. IS 303 grade plywood ove the aluminium frame of approved make , finished / fixed with 1 mm thick laminate , Seude finish of approved make & shade fixed with adhesive over the ply surface				
	The cost to include provision for extra framewark as necessary to make provision for skirting, switch boxes, light fittings/ lights etc, making provision for laying conduit etc.				
	panelling , the height upto False ceiling will be considered. Makes: boards /ply :Century / Fiden/Austin, Laminate:- Century/ Signature/Elvee .\				
4.2	Wall panelling with 12 mm thk gypsum with top coat finish	sqm	55		
	Providing Aluminium frame (INDIAL/JINDAL) of size 50x25 x1.8 mm thk (finished) comprising of horizontals and verticals at, 600 mm c/c or part thereof with insertion of 25 mm thk glass wool, vertically and horizontally fixed firmly to walls / floors / RCC roof etc.				
	Providing 12 mm thk. gypsum ove the aluminium frame of approved make , finished with required top coat				
	The cost to include provision for extra framewark as necessary to make provision for skirting, switch boxes, light fittings/ lights etc, making provision for laying conduit etc.				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
	<p>NOTE : For measurement of the area of the panelling , the height upto False ceiling will be considered.</p> <p>Makes: boards /ply :Century / Fiden/Austin, Laminate:- Century/ Signature/Elvee .\</p>				

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
4.3	Wall panelling with 8 mm thk ply with Texture laminate finish	sqm	6		
	Providing Aluminium frame (INDIAL/JINDAL) of size 50x25 x1.8 mm thk (finished) comprising of horizontals and verticals at, 600 mm c/c or part thereof with insertion of 25 mm thk glass wool, vertically and horizontally fixed firmly to walls / floors / RCC roof etc.				
	Providing 8 mm thk. IS 303 grade plywood ove the aluminium frame of approved make , finished / fixed with 1 mm thk Textured Laminate finish of approved make & shade fixed with adhesive over the ply surface				
	The cost to include provision for extra framewark as necessary to make provision for skirting, switch boxes, light fittings/ lights etc, making provision for laying conduit etc.				
	NOTE : For measurement of the area of the panelling , the height upto False ceiling will be considered. Makes: boards /ply :Century / Fiden/Austin : Veneer : Century, Green or Euro				
5	Providing and fixing 12 mm soft board, padding, and upholstered with high end fabric as approved over existing ply surface The edges of soft board to have Teak wood moulding with pu polish with tightened edges.	sqm	4.6		
6	Providing and fixing lacquered glass on existing ply surface	sqm	2		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
7	Supplying and fixing in position pin up boards, fabricated with 6mm ply covered with 12 mm soft board, padding, and upholstered with fabric costing rs. 150/- per mtr.	sqm	6		
8	DOORS				
8.1	Providing and Fixing full glass door (D), twin style made out of 12 mm thick toughened glass, in patch fittings, and with heavy duty floor spring with SS cover plate. The doors to be provided with locking arrangement in patch fittings as well as ss 25 mm dia, and approx. 600 mm long approved model handles.	no	1		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
8.2	Providing and fixing semi-glazed door(D1) 900x2100 mm of 32mm thick non-decorative type block board core of wood strips and frame of 1st class hard wood inserted inside aluminium frame as per design and including cover mould of 12x50mm , finished with 1mm thick Laminate on both sides, as per instruction . The Door edge will finished with 2mm thk. edge banding as per matching shade .Only ISI marked flush doors should be used. The door shall include 8 mm clear glass . The glass shall be supported with teak wood beading and melamine polished. Stoppers should be provided at skirting level to prevent the door from hitting the wall. Cylindrical lock cum handle to be provided in the flush door. SS heavy duty hinges to be used for fixing the door to the frame. Door stopper at bottom to be provided also SS Hydraulic door closer to be provided in each door.	no	6		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
8.3	Providing and fixing solid flush door(D2) 900x2100 mm of 32mm thick non-decorative type block board core of wood strips and frame of 1st class hard wood inserted inside aluminium frame as per design and including cover mould of 12x50mm , finished with 1mm thick Laminate on both sides, as per instruction . The Door edge will finished with 2mm thk. edge banding as per matching shade .Only ISI marked flush doors should be used. Stoppers should be provided at skirting level to prevent the door from hitting the wall. Cylindrical lock cum handle to be provided in the flush door. SS heavy duty hinges to be used for fixing the door to the frame. Door stopper at bottom to be provided also SS Hydraulic door closer to be provided in each door.	no	1		
9	Supplying and fixing etching film on all clear glasses as per design/line and shape and as instructed by Architect	sqm	15		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
10	Roller Blinds (Alps industries/Legstrong or equivalent) Providing and fixing Roller Tube of extruded aluminium alloy 38-mm O.D. with a minimum wall thickness of 1mm duly anodized. Clutch shall be wrap spring design with high strength fibre glass reinforced polyester assembly and high carbon steel springs to transmit motion from driving to driven members of clutch mechanism. IDLER shall be of high strength Fibreglass reinforced polyester. INSTALLATION BRACKETS shall be of tomised steel powder coated. BOTTOM WEIGHT of the blind shall be provided with aluminium tube powder coated. FABRIC BLINDS will be roller Fabric blinds as per following specification Composition 80% + PVC, Thk. 0.8mm +, UV Block 70%, flame resistant	sqm	18		
11	BUILT IN FURNITURE				
11.1	Providing, fabricating and fixing (400 mm. deep) low height 750mm/900mm Laminated storages consisting of 19mm ply, at top, bottom, sides, horizontal & vertical partition, drawers and shutters with 6mm thick ply backing and with 1mm thk.laminate finish on all exposed faces and enamel paint on inside surface.Rate to include cost towards fixing of stainless steel hinges, tower bolts, locks etc. complete in all respects .	sqm	25		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
11.2	Providing, fabricating and fixing (400 mm. deep)full height Laminated storages consisting of 19mm ply, at top, bottom, sides, horizontal & vertical partition, drawers and shutters with 6mm thick ply backing and with 1mm thk.laminate finish on all exposed faces and enamel finished on inside surface.Rate to include cost towards fixing of stainless steel hinges, tower bolts, locks etc. complete in all respects .	sqm	15		
11.3	Providing, fabricating and fixing (300 mm. deep) OverHead Laminated storages consisting of 19mm ply, at top, bottom, sides, horizontal & vertical partition, shutters with 6mm thick ply backing and with 1mm thk.laminate finish on all exposed faces and enamel paint finish on inside surface.Rate to include cost towards fixing of stainless steel hinges, tower bolts, locks etc. complete in all respects .	sqm	1		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
12	Providing and making (10+1=11) seater Meeting table in PU Lamination finish of highest standard for size 4280x1200x50 mm table top as per design, made of 19mm ply (Green/century/austin /) with supporting pedestal below of size 3680x600x700 mm. with required storage cabinets and wire management system etc.The pedestal is to be finished in 1mm thk. laminate (Century/ Signature / elvee) with required grooves as per design. All inner surface of the cabinets below is to be paint finish . Rate is to be inclusive of required wire management system , cut-outs on top for fixing pop-up boxes, all necessary hardware - SS cabinet handles 150mm long, locksets, self closing hinges, spring loaded shutter towerbolt inside complete as per architects drawing and approval.	no	1		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
13	EXECUTIVE TABLES				
13.1	Providing and making CABIN TYPE-1 Table of size 2100x1000 x750mm. with 40 mm thk projected top made out of 19mm ply (Century/austin/fiden) with 1no. drawer of size 150x500x450 and 1no cabinet with shutter below of size 542 x 750 x 450 finished with enamel paint on inside surface and 4mm thk. veneer with PU Lamination polish on all exposed surface . Front fascia of the table to have 4 mm. thk. grooves with deep polish. Side credenza of size (1000x450x750) with 1 no. drawer (150x400x300) with cpu stand in same finish to be provided. Rate is to be inclusive of keyboard tray ,foot rest, all necessary hardware - SS cabinet handles 150mm long, locksets, self closing hinges, spring loaded shutter towerbolt inside with all cabinet hardwares to be Hettich or equivalent complete as per architects drawing and approval.	no	1		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
13.2	Providing and making CABIN TYPE-2 Table of size 2100x825x750 mm. with 40 mm thk projected top made out of 19mm ply (century/austin/Fiden) with 1no. drawer of size 150x450x400 and 1no cabinet with shutter below of size 542 x 500 x 400 finished with 0.8 mm thk. balancing laminate on inside surface and 1mmthk. bi-colour laminate on all exposed surface . Front fascia of the table to have required grooves as per design. Side credenza of size (1000x450x750) with 1 no. drawer (150x400x300) with cpu stand in same finish to be provide. Rate is to be inclusive of keyboard tray ,foot rest, all necessary hardware - SS cabinet handles 150mm long, locksets, self closing hinges, spring loaded shutter towerbolt inside with all cabinet hardwares to be Hettich or equivalent complete as per architects drawing and approval.	no	1		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
13.3	<p>Providing and making Tables at Low.Ht. Cubicle of size 1800x750x750 mm. with 40 mm thk projected top made out of IS-303 grade,19mm thk ply (Fiden,Austin, Century) in 1mm thk. laminate finish(century/signature/Green). The lower base of the table will be made out of 19mm ply with 1no. drawer of size 100x500x400 and 1no cabinet with shutter below of size 542 x 700 x 400 finished with enamel paint finish on inside surface and 1mm.thk. bi-colour laminate on all exposed surface . Front and side fascia of the table to have 25mm. projected corner surface with 6mm.thk. grooves as per design. Side credenza of size (900x400x750) with 1 no. drawer (100x400x300) , cpu stand in same finish to be provided. Rate is to be inclusive of keyboard tray ,foot rest, all necessary hardware - SS cabinet handles 150mm long, locksets, self closing hinges, spring loaded shutter towerbolt inside with all cabinet hardwares to be Hettich or</p>	no	3		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
14	MODULAR FURNITURE & CHAIRS				
14.1	Workstation (ISO in MDF make or Equivalent)				
	65-70 mm L shape WORKSTATION MAIN TABLE TOP : 1500W /1500L X 600D X 750HT.TABLE TOP AND 1200HT PARTITIONS Table top : 25mm thick MDF Board finished with 2mm edge lipping. Main Frame : 65-70mm thk with Fabric tile, Glass Marker above table top and Laminate Tile Below Table Top Return Frame : 65-70mm thk with Fabric tile, Fabric Magnetic above table top and Laminate Tile Below Table Top Support : MS Brackets and Gable Ends Wire Management : Raceway provided below table top for Power and Skirting Level for Data & 65 mm Dia Wire Manager Cap Included CPU Trolley 1 No. Per Work Station Included ABS Keyboard Tray 1 No. Per Work Station Included Mobile Pedestal 1 No. Per	no	10		
14.2	GM/DGM chairs Model: Click High Back Leatherette Chair Click High Back Chair Leatherette Seat and Back Synchro Mechanism Two Way Adjustable Arms (Height and Width) With Tilt Tension Adjustment and Upright Locking Chrome Base Make: Featherlite / Durian	no	1		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
14.3	AGM Chair Model: Click Medium Back Leatherette Chair Click Medium Back Chair Leatherette Seat and Back Synchro Mechanism Two Way Adjustable Arms (Height and Width) With Tilt Tension Adjustment and Upright Locking Chrome Base Make: Featherlite / Durian	no	1		
14.4	Staff Chair Model: Click Medium Back Fabric Chair Click Medium Back Chair Cushioned Seat and Back Synchro Mechanism Two Way Adjustable Arms (Height and Width) With Tilt Tension Adjustment and Upright Locking Chrome Base Make: Featherlite / Durian	no	11		
14.5	Visitor's Chairs Model: Advantage Medium Back Medium Back Permanent Contact Fixed Arms Revolving and Tilting Chair With Tilt Tension Adjustment And Upright Locking Nylon Base Make: Featherlite / Durian	no	12		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
14.6	Conference Room Chair Model: Click Medium Back Fabric Chair Click Medium Back Chair Cushioned Seat and Back Synchro Mechanism Two Way Adjustable Arms (Height And Width) With Tilt Tension Adjustment and Upright Locking Chrome Base Make: Featherlite/ Durian	no	11		
14.7	Lunch Room Chairs Model: Eves PVC Back and Seat Metal Frame Fixed Legs Make: Featherlite/Durian	no	6		
14.8	Manager's Chair Model: Bravo Medium Back Leatherette Chair Bravo Medium Back Chair Leatherette Seat and Back Centre Tilt Mechanism Fixed Arms Chrome Base Make: Featherlite / Durian	no	3		
14.9	Sofa Model: 238-2S (Pearl-2 Seater) Leatherette Sofa Anti Termite Treated Seat Cushioned Seat and Back With Armrest Chrome Frame	no	5		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
15	OTHER TABLES				
15.1	Providing and making Reception table of size 1600x550x750 made of 19mm ply IS-303 (Fiden/austin/century) with 1 nos.drawer of size 125x450x450 and 1no cabinet(450x500) on each side with shutter below finished with 1mm thk. laminate on all exposed surface as per approved shade. All inner surface of the table to be finished with enamel paint finish (century/signature/elvee). The table should consist of visitor's ledge at a height of 1050mm with top and front fascia in PU finish with slits in core cutting including provision for backlit illumination . Rate should be inclusive of required standard metallic keyboard tray, wire management system , foot rest, all necessary hardware - SS cabinet handles 100mm long, locksets, self closing hinges, spring loaded shutter towerbolt inside, with all cabinet hardwares to be Hettich or equivalent complete as per architects drawing and approval.	no	1		
15.2	Providing and making centre Table with 19mm ply IS-303 with 1mm thk. laminate finish and 10mm thk.glass top as per design	no	1		
15.3	Providing and making side Table with 19mm ply IS-303 with 1mm thk. laminate finish and 10mm thk.glass top as per design	no	5		

SL No.	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
15.4	Providing and making dining table with size of 1875 x725x35 mm , made with 19mm ply IS-303 and finished with 1mm thk. laminate . The ply base top will have 19 mm thick granite top over it . Rate will include making of padestal in s.s. structure including all hardwares complete in all respects	no	1		
16	MISCELLENEOUS ITEMS				
16.1	Supplying and Fixing Wall covering as per shade selcted by the Architect	sq.m.	35		
16.2	Providing and fixing of 12mm. Thk. MDF board on aluminium frames over the false ceiling and will be extended upto the rcc ceiling for sound insulation.	sq.m.	9		
16.3	Providing and fixing belgium 6mm thk. Mirrors for toilets	sq.m.	1		
16.4	Providing and making soffit of depth 150-250 mm.made out of 19mm solid ply with enamel paint finish for fixing roller blind as well as AC indoor unit plate/pipeline installation complete as per direction	Rmt.	20		
16.5	Providing and making shutter box for rolling shutter at entrance with frame made out of 50x25x2 mm thk aluminium tube with 16mm MDF - exterior grade cladding and finally finished with acrylic paint as per direction	sq.m.	3		
GRAND TOTAL					