



शुद्धिपत्र/ Corrigendum

Date: 21.08.2018

Please refer to Bank's Tender Ref. no. 2019/1372/NDO/PREMISES dated **August 10, 2018** "HVAC Works including supply, installation, testing and commissioning etc. in SIDBI's office premises at Atma Ram House, 1, Tolstoy Marg, New Delhi".

The following changes have been made in the Tender through this Corrigendum.

Sr. No.	Reference	As per tender	Changes made
1	Page No.3 – Item No.6 - Financial Bid	<p><u>LT Main (Panel)</u> Supply, installation testing and commissioning of cubical type main MB panel board suitable for three phase 415 V 50 Hz and rupturing capacity at 415 V fabricated from minimum 2MM thick CRCA sheet, powder coated through seven tank process faciling for pricking and degreasing complete with following mounting, inter-connection etc. as required.</p> <p><u>(Main Electrical Panel)</u> Incomer 250 Amp MCCB 35 KA 4 POLE 1 No. Busbar 250 Amp copper 4 strip sleeved Outgoing 150 Amp TPN MCCB 16 KA 1 No. (32 HP OUT DOOR UNIT) AND 1 No. (48 HP OUT DOOR UNIT) 63 Amp TPN MCCB 16KA (AHU) 1 No. 2 No. spare</p>	<p><u>LT Main (Panel)</u> Supply, installation testing and commissioning of cubical type main MB panel board suitable for three phase 415 V 50 Hz and rupturing capacity at 415 V fabricated from minimum 2 MM thick CRCA sheet, powder coated through seven tank process faciling for pricking and degreasing complete with following mounting, interconnection etc. asrequired.</p> <p><u>(Main Electrical Panel)</u> Incomer 250 Amp MCCB 35 KA 4 POLE 1 No. Busbar 250 Amp copper 4 strip sleeved Outgoing 63 Amp TPN MCCB 16 HP ODU 5 No. 6 No. spare Indicating lamps RYB Voltmeter with SS 0 to 500 including MCB CT 250/5 Ammeter with selector switch 0 to 250 A</p>

		Indicating lamps RYB Voltmeter with SS 0 to 500 including MCB CT 250/5 Ammeter with selector switch 0 to 250 A	
2	Page No.3 – Item No.5 - Financial Bid	Fabrication, supplying and fixing of angle iron stand in welded construction made out of following sizes of MS angle iron complete with painting one coat of red oxide primer and two coat of synthetic enamel paint of approved brand etc. complete as reqd. for fixing outdoor units for VRV/VRF system complete as required.	Fabrication, supplying and fixing of angle iron stand in welded construction made out of following sizes of MS angle iron complete with painting one coat of red oxide primer and two coat of synthetic enamel paint of approved brand etc. complete as reqd. for fixing outdoor units for VRV/VRF system complete as required. (SIZE as per actual requirement)
3	Page No.4 – Item No.13 - Financial Bid	SUPPLY FIXING TESTING AND COMMISSIONNG OF AIR COOLED DUCTABLE SPLIT UNIT WITH SCROLL COMPRESSOR AND CORD LESS REMOTE CONTROL AS PER SPECT. OF FOLLOWING SIZE AND COMPLETE WITH INDOOR AND OUT DOOR UNITS AND WITH CONTROL AND POWER CABLE AS REQUIRED AND COMPLETE IN ALL RESPECT - 8 HP	SUPPLY FIXING TESTING AND COMMISSIONNG OF TREATED FRESH AIR UNIT OF FOLLOWING CAPACITY. 8HP / 6.8 TR
4	Annexure 3, 4 , 5 on Page Nos.55, 56, 57 – Technical Bid	The words “Modular and other Furniture including Supply and Installation”, wherever appearing in the Formats/Annexures, may be read as “HVAC works including supply, installation, testing and commissioning etc.	

All other terms and conditions shall remain same as mentioned in our Tender Ref. no. 2019/1372/NDO/PREMISES dated August 10, 2018.

Kindly keep on checking our website www.sidbi.in regularly to get latest updates regarding this tender notice.

Bank reserves the right to change the dates, timings mentioned above or elsewhere mentioned in the RFP, which will be communicated by placing the same as corrigendum under Tender section on Bank's web-site.