



**Small Industries Development Bank of India
SIDBI Tower, 15, Ashok Marg, Lucknow – 226 001**

**Tender Document
(Price Bid - to be submitted in Envelope II)**

Name of Work- Supply, Installation, Testing and Commissioning of 40 KVA Silent DG with AMF Panel set for SIDBI Officers' Residential flats at Kings Apartment, Mall Avenue, Lucknow – 226 001 under buyback of existing DG set of same capacity.

Name of the Tenderer

SL.NO	DESCRIPTION	UNIT	QTY	UNIT RATE IN ₹	TOTAL AMOUNT IN ₹
I	OUT DOOR ACOUSTIC ENCLOSED CANOPY TYPE DG SET 40 KVA CONSISTING OF FOLLOWING	Set	1		
1	Supply, receive, store, unpack at site, install, testing and commissioning of Appropriate BHP prime rated diesel generating set coupled to 40 KVA Alternator with Electronic Governor, 3 ph, 50 Hz, 415V, along with Radiator type of cooling and associated equipment complete set including necessary appropriate armoured cabling as specified in the technical specification and civil works if required for proper installation of the D.G.Set				
1.1	Built in AMF control panel with battery charger including suitable isolator as per the "Technical specification for Diesel Generator set" serial No.1.3.1 enclosed				
1.2	AVM pads 'S' Type Kushi foot mounting with accessories				
1.3	Residential Quality Silencer (Includes flexible coupling) with cladding as per specification.				
1.4	Fuel Tank.				
1.5	Supply and Installation of Batteries with stand with initial charging.				
1.6	Cable adopter box as per site requirement.				
1.7	CABLING AND EARTHING:-				

	Power and control cabling, connection to existing panels. Complete earthing system (2 nos each for neutral and 2 for body) with earth pit and earthing strip connections.				
1.8	Diesel pump motor with starter control and discharge piping arrangement for pumping diesel from barrels to built in day tanks.				
2	EXHAUST SYSTEM	Set	1		
2.1	Exhaust pipes arrangements as required to suit conditions and statutory requirements, if any.				
3	STATUTORY & CEA APPROVALS	Lump sum	1		
3.1	Liasioning, preparation of working drawings and obtaining approval and receiving the safety certificate for energisation. clearance from Electricity Authority, Municipality , Pollution Control Board (as per CPCB Norms –II or latest) etc. as applicable for installation and running DG set				
3.2	Preparation of As built drawings after commissioning.				
4	AMC cost after initial warranty period of 2 years. The warranty & AMC will be comprehensive and all cost of repairs / maintenance including change of any part will be borne by the successful tenderer. The AMC payments will be released six monthly after successful completion of				

	the period. The cost of replacement of oil, lube, etc. will be payable by SIDBI at standard rates during Warranty & AMC period.				
	1. For 1 st year	Lump sum	1		
	2. For 2nd year	Lump sum	1		
	3. For 3rd year	Lump sum	1		
5	Buy back of existing DG Set (40 KVA) Kirloskar make along with accessories in as is where is condition. Amount quoted against this item shall be paid by the contractor (agency) to SIDBI. Buy back amount may be quoted after inspection of the existing old DG Set and considering removing and transporting / loading / unloading etc. of the same from site after delivery / installation of new DG Set.				
TOTAL (Sr 1 + Sr 2 +Sr 3 + Sr 4 –Sr. 5)					

Total quoted Amount in Words :-

Note – The successful tenderer will be decided on the basis of the total amount quoted including AMC & Buyback.

Signature :
Name of the Tenderer :

Date / place
Seal

:
:
