



PART II-(Price bids)

Sub: Internal Painting with misc. civil & plumbing work to SIDBI OFFICERS QUARTERS AT Meenaxi Appt., 'B' Wing, Gokuldham, Goregoan(E), MUMBAI

SCHEDULE OF QUANTITY

Sl.No.	Description of Items	Unit	Quantity	Rate (Rs.)	Amount
1	Internal Patch Plaster: within the flat: Wall & ceiling Removing existing damaged/ cracked plaster, Preparing the surface for internal plaster, filling the joints of brick and beam/column by filling polymer modified mortar pocking the metals randomly, racking the fresh joints, providing and fixing double layer of expanded GI metal mesh 200mm width, 100mm on either side of the junction and after due preparation, filling the joints of bricks applying rough zarra coat of ready mix mixed with approved polymer replacing the brick skin, and finally applying single coat of 15mm thick waterproof internal plaster in perfect line and level including finishing the surface with 2mm thick fine POP punning, providing scaffolding, curing all complete as directed by the Bank's Engineer	Sq.ft	1000		
2	Applying Chemical Treatment on wall before painting: Particularly common wall with toilets Providing and applying two coats of approved chemical/polymer as M/s. Pidilite, Mac Bouch, Chemisol over a coat of described Primer over a pilled off and damaged wall surface all as directed by the Bank's Engineer.	Sq.ft	1000		
3	Synthetic Enamel paint: Doors & Grills Metallic/ Wooden surface painting: Removing by scrapping old paint and cleaning with rust remover to prepare the old painted surfaces suitably and providing and applying one coat of metal primer and two or more coats of 1st quality synthetic enemel paint of approved make shade to steel work viz. grills, gate, weld mesh, wire mesh, rolling shutters, etc. as per specifications and finishing smoothly including scaffolding etc. complete as directed.	Sq.ft	2400		
4	Plastic Emulsion-(Interior ceiling of flats/ staicase area) Scrapping of existing paint from the walls and ceiling with sand paper, cleaning, filling cracks with specified crack filler, filling with putty, levelling and applying one coat of primer and two or more coats of Oil Bound Distemper (OBD) on ceilings and walls of approved shade including cost of labour, tools etc. complete.	sq.ft	22,000		
TOTAL				Rs.	
Total in words: Rupees					

TENDER TENDER FOR INTERNAL PAINTING WITH CIVIL & PLUMBING WORK
AT Meenaxi Appt., 'B' Wing, Gokuldham, Goregoan(E), MUMBAI



Note: Old specifically toilet CP fitting fixtures/ Door/Window locks/handles ,
all the items which has been replaced with new items shall be kept in the same flat with due information
to Banks Caretakers and the occupants of the flats.

Place

Name of the Tenderer

Date

Signature of Contractor with seal